Items of work.	*Per.*	*Quantity.*
Earthwork excavation and filling basement...	C. yd.	245
Concrete in chunam	C. ft.	4,948
Burnt stone in chunam	,,	2,186
Burnt brick in chunam with scaffolding	,,	8,913
Do arch work	,,	581
Burnt stone slabs, dressed	S. ft.	789
Chunam pointing	Sqr.	3·76
Chunam plastering	,,	134·47
White and color washing	,,	134·47
Burnt stone pillars with caps and base with nice dressing ...	Each	4
Teakwood doors pannelled with hinges, bolts and clamps, etc., complete	Sq. ft.	327
Teakwood pannelled windows with glazed shutters inside and pannelled shutters outside with iron bars, clamps, hinges and bolts, etc., complete	,,	480
Teakwood fanlights over windows with glazed shutters, etc., complete	,,	113
Teakwood flat ventilators with iron bars, clamps, etc., complete	,,	72
Teakwood circular do do ...	Each	2
Teakwood finials with scilicate painting	,,	4
Do at eaves, small	,,	8
Teakwood wrought and put up with wood oiling	C. ft.	344·10
Roofing with first class Mangalore tiles with teak reepers, etc., complete	Sqr.	48·22
Cuddapah slab flooring with 3″ concrete bedding and cement pointing complete	,,	18·31
Silicate pointing	,,	26·42
Ridge tiles set in mortar	Rft.	242
Zinc sheets	Sq. ft.	174
Teakwood eave boards, ornamental	R. ft.	474
Brick masonry binding wall with plastering	,,	82
Black board with shell line	Each	10
Teakwood pegs with painting	,,	82
Date stone with chiselling, numbering and painting ...	,,	1
Constructing a drain with box drain to lead off and forming roads in court yard in front and gravelling around the building	Lump sum	
Fixing flat iron bars at ends of eaves	C. W. T.	6
Iron clips fixing, etc.	Each	90
Levelling ground and clearing site	Lump sum	
Constructing a latrine with urinel	Lump sum	
Flooring with concrete and plastering with chunam over it ...	Sqr.	5·87

Note.—The materials, *viz.*, stones, bricks, tiles, Cuddapah slabs already collected should be accepted at the rates fixed by the Executive Engineer.

V. AIYASWAMI IYER,
Executive Engineer.

HASSAN DIVISION.

Notification dated 9th August 1912.

There is a road slip in the 8—149th mile of the Bangalore-Mangalore road near Marnahalli village. The public are hereby informed that a temporary road is opened to the east of the Travellers' Bungalow which should be used somewhat cautiously.

V. R. NIJAGAL,
Executive Engineer.

KADUR DIVISION.

Notice dated 24th July 1912.

The attention of the public is invited to the notification published in the *Mysore Gazette*, dated 1st August 1912, calling for tenders for opening out a feeder from Nagannan Anikat to Tarikere Valley and enlarging the Ramanaikankere tank of Tarikere Taluk, Kadur District.

Notice dated 24th July 1912.

The attention of the public is invited to the notification published in the *Mysore Gazette*, dated 1st August 1912, calling for tenders for Improving the Chik Patnagiri Anikat and Channel, Kadur Taluk, Kadur District.

R. S. NAVARATNA,
Executive Engineer.